

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County, Sec. 26 Twp. 20S Rge. 26W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW SE SE

Lease Owner Dunne-Gardner Petroleum, Inc.  
Lease Name Goodman Well No. 1  
Office Address Suite 250, 200 West Douglas, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole

Date Well completed September 1, 1979  
Application for plugging filed September 1, 1979  
Application for plugging approved September 1, 1979  
Plugging commenced September 1, 1979  
Plugging completed September 1, 1979  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation Depth to top Bottom Total Depth of Well 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	340'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 540', 60 sacks cement  
Mud to 330', 30 sacks cement  
Mud to 40', plug, 1/4 sack hulls  
10 sacks cement, 5 sacks in rathole

09-13-1979

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Donald E. Hunt (employee of owner) (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald E. Hunt  
Suite 250, 200 W. Douglas, Wichita, KS 67202  
(Address)

10th day of September, 1979

Dorothy M. Mikish Notary Public.



My commission expires March 1, 1982

15-135-21663-00-00

DRILLERS LOG

#1 GOODMAN  
NW SE SE Section 26-20S-26W  
Ness County, Kansas

OPERATOR: DUNNE-GARDNER PETROLEUM, INC.  
Suite 250, 200 West Douglas  
Wichita, Kansas 67202

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.  
Suite 250, 200 West Douglas  
Wichita, Kansas 67202

COMMENCED: August 23, 1979

COMPLETED: September 1, 1979

CASING RECORD: 8-5/8" @ 340' w/250 sx

FROM	TO	DESCRIPTION
0	347	Sand and shale
347	480	Blue shale and sand
480	1170	Red bed and shale
1170	1380	Sand
1380	1636	Shale
1636	1668	Red bed - shale
1668	1700	Anhydrite
1700	2065	Shale and shells
2065	2670	Lime and shale
2670	2925	Lime
2925	3710	Shale and lime
3710	3892	Lime
3892	4065	Lime and shale
4065	4500	Lime
4500		Rotary total depth

STATE OF KANSAS )  
                          )  
COUNTY OF SEDGWICK)

09-13-1979

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

Donald E. Hunt  
Donald E. Hunt

Subscribed and sworn to before me this 10th day of September, 1979.

My appointment expires:  
March 1, 1982

Dorothy M. Michals  
Notary Public

