

15-165-00342-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rush County, Sec. 26 Twp. 16S Rge. 17W (E) (W)

Location as "NE/CNW&SW" or footage from lines NE NE SE
Lease Owner Frontier Oil Company
Lease Name Stegman "B" Well No. 1
Office Address 1720 Wichita Plaza Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed March 25 1964
Application for plugging filed March 25 1964
Application for plugging approved March 25 1964
Plugging commenced March 25 1964
Plugging completed March 25 1964
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3571 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	222'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeeze 125 sx. poz mix.
Down 8 5/8" csg. w/pump truck.

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1964
03-31-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company
Address Box 173 -- Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Maxine V. Head (employee of owner) of ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Head

1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of March, 1964

Jean Kollar

My commission expires 5-22-66

Notary Public.

15-165-00342-00-00

DRILLERS LOG

Stegman "B" No. 1

CASING RECORD:	COMPANY:	Frontier Oil Company	DESCRIPTION:
8 5/8" @ 222'	CONTRACTOR:	Red Tiger Drilling Co.	NE NE SE
w/135 sx cement	COMMENCED:	March 14, 1964	26-16S-17W
	COMPLETED:	March 25, 1964	Rush County, Kansas
			ELEVATION:
			1999 DF
TOTAL DEPTH: 3571'			2002 RB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil, Shale & Rock	0	223	
Shale, Shells & Sand	223	519	
Dakota	519	760	
Red Bed	760	1131	
Anhydrite	1131	1165	
Shale & Shells	1165	1320	
Shale	1320	1558	
Shale & Shells	1558	1610	
Shale & Salt	1610	1795	
Lime & Shale	1795	3016	
Topeka	3016	3034	
Lime	3034	3199	
Lime & Shale	3199	3280	
Shale	3280	3298	
Lansing-Kansas City	3298	3350	
Lime	3350	3540	
Shale	3540	3545	
Conglomerate	3545	3554	
Arbuckle	3554	3571	

RECEIVED
STATE CORPORATION COMMISSION

MAR 31 1964
03-31-1964
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Head
Maxine V. Head

Subscribed and sworn to before me this 30th day of March, 1964.

James Hollan
Notary Public

My Commission Expires:

5-22-66