

LEASE NAME Roth "B"

WELL NUMBER #1

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 26 TWP. 16 RGE. 17 (N) or (W)

COUNTY Rush

Date Well Completed 10-28-67

Plugging Commenced 12-14-94

Plugging Completed 12-14-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Ks. 67601-0458

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Gas

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-12-94 (date)

by Mr. Lacy (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached?

Producing Formation Topeka Depth to Top 3055 Bottom 3061 T.D. 3114

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Topeka	Water & Gas	3055'	61	8 5/8"	209	--
				4 1/2"	3152	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed. From feet to feet each set
Hooked to 8 5/8" - Pumped 1 1/2 Bbl. & pressured to 500#. Hooked to 4 1/2" & mixed 200# Hulls and 150 sx. 65/35 Poz., 8% gel with 100# Hulls in first of cement. Max Press = 800#. SIP-2000#

Name of Plugging Contractor Allied Cementing License No.

Address Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458

SUBSCRIBED AND SWORN TO before me this 14th day of Dec., 19 94

Linda K. Pfannenstiel Notary Public

My Commission Expires: 2/5/96
USE ONLY ONE SIDE OF EACH FORM

