

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,211-00-00

LEASE NAME Urban

WELL NUMBER 1

SPOT LOCATION SE SE SE

SEC. 24 TWP. 16 SRGE. 17 ~~KRXK~~(W)

COUNTY Rush

Date Well Completed 6-21-84

Plugging Commenced 6-21-84

Plugging Completed 6-21-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Scheck Oil Operations

ADDRESS P. O. Box 52, Gorham, KS 67640

PHONE # (913) 637-5342 OPERATORS LICENSE NO. 9292

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3606' RTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	367'	8 5/8"	367'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3606' - 1080'

50 sks cement @ 1080'

50 sks cement @ 390'

40 sks cement @ 10'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well is filed that the same are true and correct, so help me God.

DENISE S. REYNOLDS
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-13-85

RECEIVED
STATE CORPORATION COMMISSION
06-27-1984
JUN 27 1984
CONSOLIDATED AND SWORN TO before me this 26th day of June, 1984
SUBSCRIPTION DIVISION
Wichita, Kansas

(Signature) Joe K. Branum

(Address) P. O. Box 506
Russell, KS 67665

Denise S. Reynolds, Notary Public

My Commission expires: February 13, 1985

15-165-21211-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Scheck Oil Operations
P. O. Box 52
Gorham, KS 67640

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Urban WELL: #1

LOCATION: SE SE SE
Section 24-16S-17W
Rush County, Kansas

ROTARY TOTAL DEPTH: 3606'

ELEVATION: 1969' K.B.

COMMENCED: 6-13-84

DATE COMPLETED: 6-21-84

CASING: 8 5/8" @ 367' with 230 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	40'	Redbed & Shale	1235'
Sand & Shale	490'	Lime & Shale	1840'
Sand	725'	Shale	2188'
Redbed & Shale	1087'	Lime & Shale	3470'
Anhydrite	1120'	Lime (RTD)	3606'


STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Joe K. Branum

Subscribed and sworn to before me this 26th day of June, 1984.

My Commission Expires: February 13, 1985.




Denise S. Reynolds, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1984
06-27-1984
CONSERVATION DIVISION
Wichita, Kansas