

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and file ONE Copy)

API # 15-101-21,691 ⁻⁰⁰⁰⁰ (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Rheem Resources, Inc. KCC LICENSE # 31283
(owner/company name) (operator's)

ADDRESS 100 S. Main, Suite 505 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-5099

LEASE Smid WELL# 1 SEC. 30 T. 20S R. 28 (~~East~~/West)

- NE - SE - SE SPOT LOCATION/QQQQ COUNTY Lane

990 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL DEA SWD/ENR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 256.45' CEMENTED WITH 190 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION _____ T.D. _____ PRPD _____ ANHYDRITE DEPTH 2068'
(G.L./R.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill with heavy mud; 1st plug at 2130' with 50 sks, 2nd plug at 1180' with 80 sks, 3rd plug at 600' with 40 sks, 4th plug at 280' with 50 sks, 5th plug at 40' with 10 sks, 15 sks rathole, total 245 sks 60/40 pos, 6% gel with 1/4# floseal per sk.
(if additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACC-1 FILED? _____

If not explain why? Sent to operator

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Anthony Martin PHONE# (316) 262-1841

ADDRESS 150 N. Main, Ste 801 City/State Wichita, Ks. 67202

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Main, Ste 801, Wichita, Ks. 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (if known?) 01-10-95 3:45 a.m.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 02-07-95 AUTHORIZED OPERATOR/AGENT: Jack W. Wharton
(signature) Vice President