

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-217550000

LEASE NAME Anderson Trust

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

2,167 Ft. from W Section Line

SEC. 33 TWP. 16 RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 3-9-98

Plugging Commenced 3-9-98

Plugging Completed 3-9-98

LEASE OPERATOR Rheem Resources, Inc.

ADDRESS 100 S. Main, Suite 505, Wichita, KS.

PHONE#(316) 262-5099 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-9-98 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	210'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Push plug to 2,090', spot 50 sax cement thru drill pipe. Push plug to 1,280', spot 80 sax cement thru drill pipe. Push plug to 600', spot 40 sax cement thru drill pipe. Push plug to 230', spot 40 sax cement thru drill pipe. Push wiper plug to 40', dump 10 sax cement to cellar. Dump 15 sax cement down rat hole and 10 sax cement mouse hole. 245 sax 60-40 poz., 6% Gel, 1/4# Floseal/sax. Plug down @6:45PM

Name of Plugging Contractor Shields Drilling, division of Shields Oil Producers, Inc. License No. 5184

Address 326 Main, Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rheem Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec-Treas Contractor (Employee of Anderson Trust) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) 326 Main, Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 16th day of March, 19 98

Keith Phillips
Notary Public

My Commission Expires: _____

