


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-101-19031-0000  
WELL PLUGGING RECORD

Lane \_\_\_\_\_ County. Sec. 33 Twp. 16S Rge. 27W (X) (W)

Location as "NE/CNW/SW" or footage from lines C SW SE  
Lease Owner Helmerich & Payne, Inc.  
Lease Name ANDERSON Well No. 2  
Office Address Box 558, Garden City, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 7 19 62  
Application for plugging filed July 8 19 62  
Application for plugging approved July 8 19 62  
Plugging commenced July 8 19 62  
Plugging completed July 8 19 62  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production --- 19 ---  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas  
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 4580 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4580 to 660 Heavy Rotary Mud  
660 to 600 20 sacks pozmix cement & Plug  
600 to 240 Heavy Rotary Mud  
240 to 183 Plug & 20 sacks pozmix cement  
183 to 35 Heavy Rotary Mud  
35 to 4 Plug & 10 sacks pozmix cement  
4 to 0 Cellar

Plugging completed at 10:15 AM July 8, 1962

RECEIVED  
STATE CORPORATION COMMISSION  
7-23-62  
JUL 23 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Helmerich & Payne, Inc.  
Address First National Bldg, Tulsa, Okla.

STATE OF Kansas, COUNTY OF Finney, ss.  
T. E. Mort (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. E. Mort  
Box 558, Garden City, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of July 1962

My commission expires July 1964

Robert N. Boyd  
Robert N. Boyd Notary Public.

14

MORT

15-101-19031-0000

Helen Anderson No. 2  
 Helmerich & Payne, Inc.  
 Section 33-16S-27W  
 Lane County, Kansas

Casing Record:

13 Jts. 8-5/8" Csg. @ 285.07 w/200 sxs. Sunset Cement.  
P&A

Commenced: 6-28-62  
Completed: 7-8-62

	<u>FROM</u>	<u>TO</u>
Surface	0	290
Shale	290	2557
Shale & Lime	2557	2731
Shale	2731	3068
Lime & Shale	3068	3159
Shale & Lime	3159	3318
Lime & Shale	3318	3525
Shale & Lime	3525	3614
Lime & Shale	3614	3818
Lime	3818	3880
Shale & Lime	3880	4028
Lime & Shale	4028	4075
Lime	4075	4184
Shale ; & Lime	4184	4225
Lime	4225	4295
Shale & Lime	4295	4382
Lime & Shale	4382	4522
Shale & Lime	4522	4580
<u>Total Depth</u>	<u>4580</u>	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUL 30 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF OKLAHOMA )  
 ) SS  
 County of Tulsa )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Helen Anderson No. 2 well, located in Section 33-16S-27W, Lane County, Kansas.

HELMERICH & PAYNE, INC.

*Lee Daniel*  
 Vice President

Subscribed and sworn to before me a Notary Public this 18th day of July, 1962.

*Margaret Bailey*  
 Notary Public

My Commission expires March 30, 1964.