

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-006280000
Drlg Completed 3-13-62

LEASE NAME Anderson

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 ? Ft. from S Section Line

1320 ? Ft. from E Section Line

SEC. 33 TWP. 16s RGE. 27 (*) or (W)

COUNTY Lane

LEASE OPERATOR Helmerich & Payne, Inc

ADDRESS P O Box 558, Garden City, KS 67846

Date Well Completed 4-4-62

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Plugging Commenced 8-29-88

Character of Well Oil

Plugging Completed 9-9-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City - Dan Goodrow

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing I Depth to Top 4207 Bottom 4218 T.D. 4700

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing I	Oil & water	4207	18	5 1/2	4322	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Packer stuck in well @4187. Backed off tbg @4102. Pulled up to 4065. Spotted 50sks 60/40Poz 6% gel w/200# cottonseed hulls from 3465 to 4065'. Pulled up above plug & circ well w/treated saltwater. Spot 20sks 60/40poz 6% gel plug from 2112 to 1860'. Spot 75sks 60/40poz 6% gel plug from 996' to surface. Pull tbg. Fill 5 1/2" csg w/cmt. Halliburton tagged TOC in 5 1/2" csg at 550' (If additional description is necessary, use BACK of this form.) (see back)

Name of Plugging Contractor Halliburton License No. _____

Address Ness City

STATE OF Kansas COUNTY OF Lane, ss.


Ken Jehlik

Conservation Division
I, Ken Jehlik, of Operator) or (Operator) of above-described well, being first duly sworn on oath, say that I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ken Jehlik KT

(Address) Box 558 Garden City, Kansas


SUBSCRIBED AND SWORN TO before me this 13th day of September, 1988



Judy J. Richmeier
Notary Public

August 15, 1992

after setting eight days. White Redimix (Dighton) filled 5½" csg with 2-¾ yards cement on 9-9-88.



15-101-60028-0000

SCHLUMBERGER

SONIC LOG

SCHLUMBERGER WELL SURVEYING CORPORATION
Houston, Texas

COUNTY
FIELD or
LOCATION
WELL
COMPANY

COMPANY Helmerich
& Payne, Inc
WELL Anderson No. 1
FIELD Wildcat
LOCATION C-SE-SE
Sec 33-T16S-R27W
COUNTY Lane
STATE Kansas

Other Surveys
LGR-Caliper
Location of Well
Elevation: K.B.: 2702
D.F.: 2700
or G.I.: 2697

Log Depths Measured From KB 5 Ft. above GL

RUN No.	<u>ONE</u>		
Date	<u>March 13, 1962</u>		
First Reading	<u>4692</u>		
Last Reading	<u>3500</u>		
Feet Measured	<u>1192</u>		
Csg. Schlum.			
Csg. Driller	<u>284</u>		
Depth Reached	<u>4699</u>		
Bottom Driller	<u>4700</u>		
Mud Nat.	<u>Gel</u>		
Dens.	<u>10.0</u>	<u>46</u>	
Mud Resist.	<u>0.255 @ 73 °F</u>	@	°F
" Res. BH	<u>0.172 @ 113 °F</u>	@	°F
" pH	<u>6.0 @ °F</u>	@	°F
" Wtr. Loss	<u>8.0 CC 30 min</u>	CC 30 min	CC 30 min
" Rmf (M)	<u>0.175 @ 75 °F</u>	<u>0.120 @ 113 °F</u>	@
Bit Size	<u>7 7/8</u>		
Spacing:			
T ₃ R ₁ L R ₂	<u>3500 To 4692</u>	To	To
T R R ₂	To	To	To
Opr. Rig Time	<u>2 hours</u>		
Truck No.	<u>2922 - Great Bend</u>		
Recorded By	<u>Jack Hall</u>		
Witness	<u>McCoy</u>		

RECEIVED
STATE CORPORATION COMMISSION