

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

CP4

API NUMBER 101-21782-0060

LEASE NAME Anderson

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 33 TWP. 16 RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 9-8-00

Plugging Commenced 1:00AM 9/8/00

Plugging Completed 5:00AM 9/8/00

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Wilton Petroleum, Inc.

ADDRESS 901 King Ave, Nyssa, OR 97913

PHONE#(316) 947-3254 OPERATORS LICENSE NO. 7775

Character of well D&A

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 9/7/00 (date)

by Steve Pfeifer (KCC District Agent's Name).

is AGO-i filed? Yes if not, is well log attached? _____

Producing Formation none Depth to Top _____ Bottom T.D. 4610

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|---------|-----|-------|--------|------------|
| | | Surface | 231 | 8 5/8 | 231.94 | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Plug @ 2140' w/50sx 5th plug @ 40' w/10sx Circulated 1st plug 15min w/48 vis mud
Plug @ 1350' w/80 sx 15 sx in rat hole plugs displaced w/mud
Plug @ 650' w/50sx total 245 sx 60/40 poz 6%gal w/1/4 flo seal by Allied
plug @ 260' w/ 40 sx completed @ 5:00 AM 9/8/00

Name of Plugging Contractor Discovery Drilling, Inc License STAT 1548

Address PO Box 763, Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Wilton Petroleum, Inc

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Peter J. Coakley FRANK S. MIZE (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) _____

SUBSCRIBED AND SWORN TO before me this 29th day of September, 2000

[Signature]
Notary Public

My Commission Expires: 11-12-2002

PETER J. COAKLEY
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 11-12-02

RECEIVED
OCT 3 2000

CONSERVATION DIVISION
Wichita, Kansas

Form 9-
Revised 05-81