

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-101-20025-00-00

API NUMBER N/A

LEASE NAME Jones

WELL NUMBER D-4

1980 Ft. from S Section LI

3300 Ft. from E Section LI

SEC. 34 TWP. 16 RGE. 27 (E) of

COUNTY Lane

Date Well Completed 12-10-91

Plugging Commenced 5-15-91

Plugging Completed 5-15-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, Kansas 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil - TA'd.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City Dan Goodrow on location

Is ACO-1 filed? If not, is well log attached? Yes

Producing Formation LKC Depth to Top 4058 Bottom 4062 T.D. 4219

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil & Water	4058	62	8 5/8	319	0
				5 1/2	4298	0
				Stage Tool	2015	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each set.

Pump 50 bfw ahead followed by 30 sks 60/40 Poz, 6% gel w/100# hulls followed by 34 bbls gel at 1 BPM @ 1000#. Follow w/90 sks 60/40 Poz, 6% gel at 1 BPM @ 1000#. Shut dn. when pressure reached 1600# @ 1/2 BPM. Close in. Top plug @ 0 to 1065' Cmt. was to surface on 5 1/2 x 8 5/8 annulus. Held 500# Bot Plug 3520' to 4060'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5293

Address Ness City, Kansas

STATE OF Kansas COUNTY OF Ness, ss.

Ken Jehlik

(Employee of Operator) or (Operator)


above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above statements, and matters herein contained and the log of the above-described well as filed therewith, and that the same are true and correct, so help me God.

(Signature) Ken Jehlik

(Address) Box 558 Garden City, Ks

SUBSCRIBED AND SWORN TO before me this 16th day of May, 1991

Judy J. Richmeier
Notary Public



MAY 20 1991
5-20-91

My Commission Expires: August 15, 1992

CONSERVATION DIVISION
Wichita, Kansas