

KANSAS

FORM CP-3
Rev. 1-8-82STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number

15-101-20,700-0000 R200 Colorado Derby Building
Wichita, KS 67202Operator's Full Name DONALD C. SLAWSON OIL PRODUCERComplete Address 200 DOUGLAS Bldg., BROADWAY & DOUGLAS, WICHITA, KS 67202Lease Name HIBBARD Well No. E #1Location C NE SE Sec. 12 Twp. 20 Rge 29 (East)(West)County LANE Total Depth 4750'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A XOther well as hereinafter indicated ☐Plugging Contractor COMPANY TOOLSAddress License No. Operation Completed: Hour: 3:30AM Day: 29 Month: 8 Year: 19 82Plugging Operations attended by Agent?: All ☐ Part ☐ None X

The above well was plugged as follows:

8 5/8" D.P. was set @ 331' w/ 225 sz. of 60-40 Poz-mix, 2% gel-3% C.C.The 1ST PLUG WAS SET @ 1290' w/ 70 sz. of 50-50 Poz mix, 4% gel-3% C.C.The 2ND ✓ ✓ ✓ @ 360' w/ 40 sz. Cmt.The 3RD ✓ was a solid bridge @ 40' using 1/2 sz. hulls & wood/rubber8 5/8" plug and 10 sz Cmt pumped 40'-0'The 5TH plug set in the Rathole w/ 15 sz. Cmt.Cementing by HalburtonAmount of Surface Casing: 331'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: R. Brarburton
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
9-2-82
SEP 2 1982Signed: Conservation Division
Wichita, Kansas
Conservation Division Agent

INVOICED

DATE 9-9-82INV. NO. 1124-18