

15-165-00224-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

1962
10-08-1962

Operator's Full Name Lario Oil & Gas

Complete Address: 301 S Market Wichita, Kansas

Lease Name Basgall Well No. 1

Location NE SW SE Sec. 5 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3756

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 3PM Day 4 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 1135' circulated with cement - 5 1/2" 3628' with 100 sax cement.
PB to 3600', Perf 3558'.

Sand to 3450', set 4 sax cement with dump bailer, pulled 2900' 5 1/2" to
480', circulated hole with heavy gel mud (24 Sax). displaced 20 sax
cement through 5 1/2" at 480', heavy mud to 160', displaced 20 sax cement
through 5 1/2" at 160', heavy mud to 30', cement 30' to 0'.

Mudding and cementing by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edwin Petty
Well Plugging Supervisor

DATE 10/10/62
INV. NO. 5819-u