

15-165-19009-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1973
08-09-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza, Wichita, Kansas 67202

Lease Name Basgall Well No. 1

Location NE SW SE Sec. 5 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3577*

Abandoned Oil Well XX Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 2:45 P Day 6 Month 8 Year 1973

The above well was plugged as follows:

Total Depth 3577* 8 5/8 csg set at 210* cwc 135 sx.

4 1/2 csg set at 3576* cw 275 sx cem.

4 1/2 csg perf. (2884-3050)

4 1/2 csg PBTB 2638* No recoverey

Pumped down annulus (4 1/2-8 5/8) with 50 sk cem. Max PP 1000 lbs. SIP 500 lbs.

Pumped down 4 1/2 csg with 20 sx cem--20 sx gel & water--released 4 1/2 plug and pumped

30 sk cem W/200 lbs hulls. Max PP 500 lbs. SIP 500 lbs. by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICE

Signed: Leo G. Massey
Well Plugging Supervisor

8/9/73
INV. NO. 7748-W