

15-165-00360-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 1973  
05-07-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Frontier Oil Company  
Complete Address 1720 VICKERS KSB&T Bldg., Wichita, Kansas 67202  
Lease Name Hartman Well No. 1  
Location NW NW SE Sec. 7 Twp. 16 Rge. (E) (W) 17  
County Rush Total Depth 3511'  
Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Knight Casing Pulling Co., Inc.  
Address Box 405 Chase, Kansas 67524 License No. 496  
Operation Completed: Hour 1:30 P Day 5 Month 5 Year 1973

The above well was plugged as follows:

Total Depth 3511' 8 5/8 csg set at 1108' cwc 425 sk.  
4 1/2 csg set at 3503' cw 250 sk cmt.  
4 1/2 csg PBTB 3476' with perf. (3147-3153)  
Set 4 1/2 wood plug at 3100' -poured 10' sand -dumped 4 sk cmt W/dump bailer. (3050-3100)  
Cutoff and recovered 2300' of 4 1/2 csg.  
Set 8 5/8 wood plug at 435' -rock & sand bridge (425-435)  
Dumped 6 yds readymix cement from 425' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3-9-73  
INV. NO. 7330-W

Signed: Leo F. Macey  
Well Plugging Supervisor