

15-125-20015-00-00

Form CP-3  
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Frontier Oil Company

Complete Address 1720 Wichita Plaza Wichita, Ks.

Lease Name Breit Well No. 2

Location SW SW NE Sec. 7 Twp. 16 Rge. 17 (E) (W) X

County Rush Total Depth 3508

Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks. License No. 436

Operation Completed: Hour 4 P Day 17 Month 1 Year 1968

The above well was plugged as follows:

Total Depth 3508' 8 5/8 csg set at 1104' cwc 425 sc.

4 1/2 csg set at 3494' cw 150 sc cement.

PBTD 3180' and perf. (3133-37)

Filled with sand to 3100' and dumped 4 sc cement with dump bailer.

Recov. 2478' of 4 1/2 csg.

Mud to 420' Set rock bridge (420-400) and filled to surface with 6 yds readymix cem.

RECEIVED

I hereby certify that the above information is true and correct as herein stated.

INVOICED

JAN 19 1968

Signed: [Signature]  
Well Plugging Supervisor

CONSERVATION DIVISION  
Wichita, Kansas

DATE 1/19/68  
INV. NO. 9115-W

01-19-1968