

15-165-00122-00-00

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials/signature

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW SE NW

SEC. 11 TWP. 16 RGE. 17

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. B-1 Lease Stegman "b"

Operator Bennett & Roberts Address ^{Drawer 103} Russell, Kans

Field _____ County Rush

Total Depth 5019 Feet.

Plugging Contractor Same & Sun Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1109' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug

at 400', displaced 20 sax cement through drill pipe, heavy mud to

200', set cementing plug and displaced 20 sax cement through drill

pipe, heavy mud to 40', set cementing plug, 1/2 sack hulls and 10

sax cement to bottom cellar.

Gilbert Leiker

By E.R. Leiker

District Conservation Agent

Date 1-18-58

PLUGGING
FILE NO. 11 T 16 R 17 W
BOOK PAGE 70 LINE 10

01-24-1958