

KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING SUPERVISOR'S REPORT

*R*

15-165-00089-00-01

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. 79-15 Location: NW NW NW

County: Rush Sec. 11 Twp. 16 Rge. 17 (E) (W)

Name of Field or Pool: \_\_\_\_\_ Total Depth: 3604

I have this date completed supervision of plugging of:

Well No. 1 Lease Stegmen "A"

Operator's Full Name Bennett & Roberts

Complete Address: Russell Kansas

Plugging Contractor: South Western Casing pulling

Address: Great Bend, Kansas License No. \_\_\_\_\_

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

If well is a rotary drilled dry hole did operators wait for you to arrive \_\_\_\_\_

If yes how long \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 2pm Day 17 Month Feb Year 1958

The above well was plugged as follows:

T.D. 3604' 8 5/8" set at 1128' Cir with cement 5 1/2" set at 3604'  
~~Flug back to 3390' & perf. at 3328'~~  
Filled with chat to 3310' and set 4 sax cement with dump bailer. Broke pipe  
at 3000' and pulled pipe out of hole. Filled hole with chunk mud to  
450' and topped with 20 sax cement, chunk mud to 200' and 20 sax cement  
chunk mud to 20' rock bridge and 10 sax cement to bottom of cellar.

02-20-1958

I hereby certify that the above well was plugged as herein stated and that I was present while the above well was being plugged.

Signed: \_\_\_\_\_  
Well Plugging Supervisor

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

was delayed with top plug on the Schmeidler LA., For Wakefield.

Reviewed: J. Lewis Brock  
Field Supervisor

Signed: Gilbert P. Linder  
Well Plugging Supervisor

Remarks:

PLUGGING  
FEB 11 11 16 R 17  
BOOK PAGE 79 LINE 15