


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 16 Twp. 16 Rge. 17W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SE SE SW
Lease Owner N-B Oil Co.
Lease Name Urban #1 Well No.
Office Address Russell, Kansas 67665
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above Section Plot

Date Well completed
Application for plugging filed
Application for plugging approved
Plugging commenced 5/12/78
Plugging completed 5/22/78
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Depth to top Bottom Total depth of Well 3571
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	1140	none
				4 1/2"	3471	2497'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded to 2900' and loaded hole with water, dumped 3 sacks cement. Shot pipe at 2790', pulled pipe into and pulled 16 joints. Fished pipe, shot pipe at 2503', pulled pipe. Set rock bridge at 420' and ran 6 yards ready mix.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

JUN 16 1978
06-06-1978

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) R. Darrell Kelso
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of May, 1978

Margaret Melcher
Notary Public.

My commission expires



15-145-01638-00-02

DRILLERS LOG

No. 1 Urban "A"

CASING RECORD:

8 5/8" @ 1140'
w/475 sx cement

COMPANY: Frontier Oil Company

CONTRACTOR: Red Tiger Drilling, Co.

COMMENCED: December 26, 1963

COMPLETED: January 5, 1964

DESCRIPTION:

SE SE SW
16-16S-17W
Rush County,
Kansas

ELEVATION: 1998 DF
2001 RB

TOTAL DEPTH: 3571'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod & Post Rock	0	40	
Post Rock	40	75	
Shale & Shells	75	500	
Sand	500	675	
Sand & Shale	675	785	
Shale	785	885	
Red Bed & Shale	885	1127	
Anhydrite	1127	1160	
Red Bed & Shale	1160	1585	
Shale & Shells	1585	1825	
Lime & Shale	1825	1920	
Shale	1920	2155	
Lime & Shale	2155	2960	
Lime	2960	3571	

FRONTIER OIL COMPANY
WICHITA, KANSAS

JAN 8 1964
01-09-1978
CONSERVATION DEPT
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

George A. Angle
George A. Angle

Subscribed and sworn to before me this 8th day of January, 1964.

Jean Shlar
Notary Public

My Commission Expires:

5-22-66