

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-20,221-000

LEASE NAME Urban "Q" #2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER _____

SPOT LOCATION SW NE SW

SEC. 16 TWP. 16 RGE. 17 W (E) or (W)

LEASE OPERATOR Frontier Oil Co.

COUNTY Rush

ADDRESS 1720 Ks. State Bk. Bldg., Wichita, Ks. 67202

Date Well Completed _____

PHONE # (316) 263-1201 OPERATORS LICENSE NO. 5140

Plugging Commenced 9/20/84

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/24/84

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 3580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1136'	none
				4 1/2"	3579'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 3220' & 4 sacks cement. Shot pipe at 2719' & 2567'.
Pipe parted & fell down hole 265'. Plugged well with 15 gel, 50 cement, 5 gel,
and 150 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling

License No. 6050

Address Box 347, Chase, Ks. 67524

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or Wichita, Kansas

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1984

My Commission expires:



Irene Hoover
Notary Public

WALTER H. MARTZ

Petroleum Geologist

112 INSURANCE BUILDING
WICHITA, KANSAS 67202

PHONE AMHERST 2-4024
AREA CODE 316

April 9, 1969

GEOLOGICAL REPORT

B-165 20221-00-00

Charles L. Carlock #2 Urban
SW NE SW Section 16-16S-17W
Rush County, Kansas

Elevation: 1989 KB; 1986 DF; 1984 GL

Total Depth: 3580'

Casing: 8 5/8" @ 1136'w/250 sacks

4 1/2" @ 3579'w/200 sacks

Contractor: Woodman-Iannitti

Spudded: March 30, 1969

Drilling Completed: April 7, 1969

Remarks: Samples saved and examined from 2300' - T.D. Geological supervision from 2930' - T.D. Kelly Bushing used for all measurements. Electric log measurements approximately 4' higher than Driller's measurements.

<u>Formation</u>	<u>Sample Tops</u>	<u>Electric Log Tops</u>
Anhydrite	1114 (+ 875) Drlr.	----
Topeka	2989 (-1000)	2988 (- 999)
Heebner	3224 (-1235)	3221 (-1232)
Toronto	3250 (-1261)	3241 (-1252)
Lansing-Kansas City	3275 (-1286)	3271 (-1282)
Base Kansas City	3506 (-1517)	3504 (-1515)
Conglomerate	3525 (-1536)	3522 (-1533)
Arbuckle	3566 (-1577)	3562 (-1573)
Total Depth	3580 (-1591)	3573 (-1584)

penetration 14'.

Zones Of Interest (Electric log measurements).

Topeka:

2988-2998 Limestone, cream-buff, dense - finely crystalline, slightly fossiliferous. Some mealy, with good porosity and good light stain. Fair show gas bubbles. No odor, no free oil. Faint taste. Fair fluorescence. (Probably gas-bearing.)

3152-3156 Limestone, cream-buff, finely crystalline, cherty, slightly chalky. Trace fair vuggy porosity and poor spotted dark stain.

RECEIVED
STATE CORPORATION COMMISSION

APR 26 1979

CONSERVATION DIVISION
Wichita Kansas