

STATE OF KANSAS STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 212 No. Market Wichita, Kansas

Rush County, Sec. 16 Twp. 16S Rge. 17W (E) (W) C SE

Location as "NE/CNW/SW" or footage from lines Lease Owner: Frontier Oil Company Lease Name: Basgall "A" Well No.: 1 Office Address: 1720 Wichita Plaza, Wichita, Kansas Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole Date well completed: January 15, 1966 Application for plugging filed: January 15, 1966 Application for plugging approved: January 15, 1966 Plugging commenced: January 15, 1966 Plugging completed: January 15, 1966 Reason for abandonment of well or producing formation: D & A

NORTH



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production: 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced?: Yes

Name of Conservation Agent who supervised plugging of this well: Gilbert Leiker Producing formation: Depth to top: Bottom: Total Depth of Well: 3574 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: SIZE 8 5/8", PUT IN 1142', PULLED OUT None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 240', plug, 25 sacks of cement thru D.P. Mud to 40'. Cement to base of cellar. 2 sacks in rathole.

RECEIVED STATE CORPORATION COMMISSION

JAN 21 1966

CONSERVATION DIVISION Wichita, Kansas

01-21-1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Red Tiger Drilling Company Address: Box 173 -- Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Maxine V. Starr (employee of owner) or former operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine V. Starr 1720 Wichita Plaza, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 1966

My commission expires 5-22-66

Notary Public.

15-145-30105-00-00

DRILLERS LOG

Basgall "A" No. 1

CASING RECORD: 8 5/8" @ 1142' w/425 sx cement

COMPANY: Frontier Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: January 6, 1966

COMPLETED: January 15, 1966

DESCRIPTION: C SE
16-16S-17W
Rush Co., Ks.

ELEVATION: 2001 DF
2004 RB

TOTAL DEPTH: 3574'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Rock & Shale	0	158	
Shale & Shells	158	180	
Shale	180	546	
Sand	546	790	
Red Bed & Shale	790	1135	
Red Bed	1135	1138	
Anhydrite	1138	1176	
Shale & Shells & Salt	1176	1875	
Shale & Shells & Lime	1875	2165	
Lime & Shale	2165	3028	
Lime	3028	3244	
Lime & Shale	3244	3320	
Lime	3320	3540	
Lime & Shale	3540	3564	
Arbuckle	3564	3574	

RECEIVED
STATE COMMISSION ON GEOLOGY

JAN 21 1966
01-21-1966
GEOLOGICAL SURVEY
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

FRONTIER OIL COMPANY

Maxine V. Starr
Maxine V. Starr

Subscribed and sworn to before me this 20th day of January, 1966.

Jean Stollas
Notary Public

My Commission Expires:

5-22-66