

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 249 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER B-165-20671-0000

LEASE NAME Burgardt

WELL NUMBER A-7

 Ft. from S Section Line

 Ft. from E Section Line
 C NW/4 NE/4

SEC. 15 TWP. 16S RGE. 17W (E) or (W)

COUNTY Rush

Date Well Completed

Plugging Commenced 10-23-86

Plugging Completed 10-29-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Lasmo Energy Corporation

ADDRESS P.O. Box 1365 Great Bend, Kansas 67530

PHONE# (316) 792-2585 OPERATORS LICENSE NO. 4678

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3632'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1179'	none
				4-1/2"	3631'	1660'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3275' and 4 sacks cement. Shot pipe @2900', 2810', 2611', 2409', 2207', 2005', pipe parted @1660', pulled a total of 49 joints of 4-1/2" casing. Plugged surface with 2 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 120 cement, 60/40 pos, 6% gel. Plugging Complete.
 (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 12th day of November, 1986

Irene Hoover
 Notary Public

My Commission Expires:



15-165-20671-00-00

DRILLERS LOG

No. 7 Burgardt "A"

ASING RECORD:	COMPANY: Frontier Oil Company	DESCRIPTION:
5/8" @ 1179.50'	CONTRACTOR: Red Tiger Drilling Company	C NW/4 NE/4
1/450 sx cement	COMMENCED: December 7, 1977	Sec. 15-T16S-R17W
1/2" @ 3,631'	COMPLETED: December 29, 1977	Rush County, Kansas
1/175 sx cement		
TOTAL DEPTH: 3,632'		ELEVATION: 2,015' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
lay	0	15	
lay, Shale & Rock	15	145	
shale	145	285	
shale & Sand Streaks	285	560	
sand & Shale	560	870	
shale & Lime Streaks	870	1016	
shale & Red Bed	1016	1152	
red Bed	1152	1166	
anhydrite	1166	1195	
shale	1195	1825	
shale & Lime	1825	2115	
lime & Shale	2115	2910	
lime	2910	3560	
conglomerate	3560	3613	
lime	3613	3632	
FD		3632	

certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

subscribed and sworn to before me this 4th day of January, 1978.

[Signature]
Notary Public STATE OF KANSAS
COMM. EX. 12345

OCT 10
10-10-1984