

KANSAS

15-101-200910000  
Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 15 1974  
3-15-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Herndon Drilling Company.  
Complete Address P. O. Box #489, Tulsa, Oklahoma.  
Lease Name Stullken Well No. 1  
Location CSW-SW Sec. 23 Twp. 20 Rge. (E) (W) 30  
County Lane Total Depth 4710'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor DNB Drilling, Incorporated,  
Address 701 First National Bank Building, Wichita, Ks License No.         
Operation Completed: Hour 7:00 PM Day 12 Month 3 Year 1974

The above well was plugged as follows:

311'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 110 Cu. Ft. cement  
thru DP from 750' to 425'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols  
Well Plugging Supervisor

DATE 3/18/74  
INV. NO. 8748-W