

15-101-30058-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION

JUL 27 1966

7-27-66

CONSERVATION DIVISION
WICHITA, KANSASJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasOperator's Full Name Birmingham & Bartlett Drilling CompanyComplete Address: 300 Kaufman Building Wichita, KansasLease Name Dumler Well No. 1Location C SE SE Sec. 22 Twp. 20 Rge. 30 (E) (W) XCounty Lane Total Depth 3755Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Empire Drlg. Co.Address: Wichita, Kansas License No. Operation Completed: Hour 4 P Day 25 Month 7 Year 1966

The Above well was plugged as follows:

RTD 3755 8 5/8 set at 185 cwcGunned pits, circulated heavy mud, set cementing plug at 600 Ft. and displaced20 sc cement thru drill pipe. Heavy mud to 175 Ft. set cementing plug anddisplaced 20 sc cement thru drill pipe. Heavy mud to 40 Ft. set cementing plug1/3 sc hulls and 10 sc cement to base of celler. Plugged rat hole with 2 sccement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/27/66INV. NO. 3638-11Signed: [Signature]
Well Plugging Supervisor