

15-101-20086-0000



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 24 1974  
1-24-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum, Incorporated,

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Beougher Well No. 1

Location CW/2-NW-SE Sec. 28 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4626'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor C & G Drilling Company,

Address 1107 Union National Bldg., Wichita, License No. \_\_\_\_\_

Operation Completed: Hour 3:00 AM Day 21 Month 1 Year 1974

The above well was plugged as follows:

279'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru DP  
from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*  
Well Plugging Supervisor

DATE 1/24/74  
INV. NO. 8444-W