

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1970
30-70
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address Suite #800-200 West Douglas, Wichita, Kansas.

Lease Name Leighton Well No. 1

Location CSW-NE Sec. 28 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4640'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas License No. 436

Operation Completed: Hour 1:00 PM Day 23 Month 3 Year 1970

The above well was plugged as follows:

296'--8 5/8" Surface casing, cement circulated with 200 Sx.
4640'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 4600'. Top perforations @ 4053'.

Pushed plug to 4000', sanded back to 3950' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing and squeezed well initially with 2 sacks hulls and 14 sacks gel and followed with 100 Sx. cement from 1200' to 775' then 11 sacks gel from 775' to 335' and followed with 25 Sx. cement from 335' to 260' then 5 sacks gel from 260' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-150#. (Recovered 1500' 5 1/2" casing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. S. Nichol
Well Plugging Supervisor

DATE 3-30-70

INV. NO. 1647-W