

15701-20019-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED  
11-8-71  
NOV 8 1971

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling, Incorporated, & Beacon Resources Corp.,

Complete Address Box #18407, Wichita, Kansas.

Lease Name McBee Well No. 1

Location NE-SW-SW Sec. 25 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4625'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Kan License No.     

Operation Completed: Hour 4:00 AM Day 5 Month 11 Year 1971

The above well was plugged as follows:

293'--8 5/8" Surface casing cement circulated with 200 Sx.  
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru  
DP from 1025' to 700'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 11-11-71

INV. NO. 4636-11