

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENCY'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
12-21-1977  
DEC 21 1977  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -165 - 20010-00-00 (of this well)

Operator's Full Name Frontier Oil Co.

Complete Address 1720 Kansas State Bank Bldg., Wichita, Kansas 67202

Lease Name Stos Well No. 1

Location SE ~~SW~~ SE Sec. 18 Twp. 16 Rge. (E) (W) 17

County Rush Total Depth 3538'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools by Allied Cementing Co.

Address Russell, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 12:30 P Day 19 Month 12 Year 1977

The above well was plugged as follows:

Total Depth 3538' 8 5/8 csg set 215' cwc 140 sk.

4 1/2 csg set 3532' cw 150 sk cem. Perf. (3526'-3238')

4 1/2 csg DV tool ser 1132' cwc 550 sk. No. pipe recovered.

Allied Cementing Co. mixed & pumped down 4 1/2 csg with 50 sk cem W/300 lbs hulls -

displaced with 25 sk gel & water & cepped with cementing plug & 50 sk cem. & shutin.

SIP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 12-21-77  
6435