

KANSAS

Form CP-3
Rev. 6-4-68

B

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-101-19026-0000

RECEIVED
STATE CORPORATION COMMISSION
MAR 30 1970
CONSERVATION DIVISION
Wichita, Kansas
3-30-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Company, Incorporated,

Complete Address Suite #800--200 West Douglas, Wichita, Kansas.

Lease Name Leighton Well No. 2

Location CNE-NE Sec. 28 Twp. 16 Rge. (E) (W) 27

County Lane Orig. RTD 4550'
Total Depth 1914'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 11:30 AM Day 23 Month 3 Year 1970

The above well was plugged as follows:

287'--8 5/8" Surface casing, cement circulated with 200 Sx.
1952'--4 1/2" casing cemented with 350 Sx. Plugged back to 1914' Top perforations @
1738'. Top of cement @ 400'-(Temperature Survey).

Pulled 4 1/2" casing and squeezed well initially with 1 sack hulls and 10 Sx. cement
then 4 sacks gel and followed with 35 Sx. cement from 1200' to 775' then 3 sacks gel
from 775' to 300' and followed with 25 Sx. cement from 300' to 225' then 5 sacks gel
from 225' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum
pump-in pressure-250#. Final shut-in pressure-200#. (Recovered 410' 4 1/2" casing).
(Mudding and cementing operations by Allied Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dinkel*
Well Plugging Supervisor

INVOICED
DATE 3-30-70
INV. NO. 1648-W