

15-101-19030-0000

Form CP-3
Rev. 6-26-62

KANSAS

4

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-3-68
SEP 3 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Helmerich & Payne, Incorporated,

Complete Address: 210¹/₂ North Main, Garden City, Kansas.

Lease Name Hall Well No. 1

Location CNE-SW Sec. 28 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4303

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Sargent's Casing Pulling Service,

Address: Box #506, Liberal, Kansas. License No. 511

Operation Completed: Hour 8:30 PM Day 29 Month 8 Year 1968

The Above well was plugged as follows:

298'--8 5/8" Surface casing , cement circulated with 200 Sx.
4238'--4 1/2" Production casing, cemented on bottom with 150 Sx. Bridge plug @ 4105',
Top perforations @ 4065'.

Sanded well back to 4005' and set 3 Sx. cement with dump bAiler. Shot casing @ 1023',

pulled casing to 900' and pumped in 9 sacks gel then followed with 100 Sx. cement.

Pulled casing to 600' and pumped in 10 sacks gel. Pulled casing to 350' and pumped

40 Sx. cement. Pulled casing and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. S. Pichok*
Well Plugging Supervisor

INVOICED

DATE 9/3/68
INV. NO. 8390-W