

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-001-28898-00-00

API NUMBER 15-001-28,898

LEASE NAME H&L Barnett

WELL NUMBER 7

1,155 Ft. from ^N Section Line

1,423 Ft. from ^W Section Line

SEC. 25 TWP. 22 RGE. 18 (E) or (W)

COUNTY Allen

Date Well Completed 15-5-00

Plugging Commenced 4-6-01

Plugging Completed 4-6-01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Harold Barnett

ADDRESS 651 1600 St. Humboldt, KS 66748

PHONE# (620) 475-3856 OPERATORS LICENSE NO. 8282

Character of Well dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-6-2001 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation none Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|------|------|--------|------------|
| Surface | 7" | top | 21.5 | 7" | yes | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set

10 sacks cement 970" to 920"

10 sacks cement 500" to 450"

40 sacks cement 250" to top

pumped through 1 inch pipe

Name of Plugging Contractor Ensminger oil License No. 6157

Address 2055 Maryland Rd. LaHarpe KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Harold Barnett

STATE OF Kansas COUNTY OF Allen, ss.

Harold Barnett (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Harold Barnett

(Address) 651-1600 St Humboldt, KS 66748

SUBSCRIBED AND SWORN TO before me this 18th day of April, 192001

Karen Kay Elder
Notary Public

My Commission Expires:



Handwritten initials 'cl'

DRILLING TIME REPORT

COMPANY: Harold Barnett

LEASE: Barnett
 NO. 7 #

API TYPE OF INDICATOR 15-001-28,898

WEIGHT ON DRILL PIPE

R.P.M. ROTARY TABLE

DATE 12-4-00

A.M.
or
P.M.

COUNTY: Allen

TWP 25 SEC 35 RANGE 20

Location TYPE OF RIG 1,155 F North

MUD-WEIGHT 1,423 F West

MUD VISCOSITY 3701 SW4, NE4, NW4

CONTRACTOR Eisminger Oil

| DEPTH | | ACTUAL DRILLING TIME | | MINUTES PER | REMARKS | BIT NO. |
|-------|-------------|----------------------|-------|-------------|--------------------------|--------------|
| FROM | TO | BEGAN | ENDED | | | |
| | Soil & Clay | 5 | | | Set 21,3' of 7" Cemented | |
| 40 | Lime | 45 | | | | |
| 27 | Shale | 72 | | | 5 5/8 Hole | |
| 9 | Lime | 81 | | | | |
| 53 | Shale | 134 | | | T.O. Hole 980' | |
| 150 | Lime | 284 | | | | |
| 130 | Shale | 414 | | | | |
| 4 | Lime | 418 | | | | |
| 39 | Shale | 457 | | | | |
| 2 | Lime | 459 | | | | |
| 9 | Shale | 468 | | | | |
| 19 | Lime | 487 | | | | |
| 63 | Shale | 550 | | 35 | Shale | 876 |
| 40 | Lime | 590 | | 1 | Coal | 877 |
| 38 | Shale | 628 | | 70 | Shale | 947 |
| 20 | Lime | 648 | | 23 | Sandy SH | 970 |
| 1 | Shale | 649 | | 10 | Shale | 980 |
| 2 | Coal | 651 | | | | |
| 1 | Shale | 652 | | | | |
| 5 | Lime | 657 | | | 10 sacks | 970' |
| 6 | Shale | 663 | | | 10 sacks | 500' |
| 9 | Sandy SH | 672 | | | | |
| 62 | Shale | 734 | | | 40 sacks | 250' to top. |
| 1 | Coal | 735 | | | | |
| 15 | Shale | 750 | | | | |
| 1 | Coal | 751 | | | | |
| 50 | Shale | 801 | | | | |
| 3 | Oil SD. | 804 | | | | |
| 3 | Sandy SH | 807 | | | | |
| 33 | Shale | 840 | | | | |
| 1 | Lime | 841 | | | | |

RECORD TIME TOUR IS CHANGED UNDER REMARKS

ACTUAL DRILLING TIME IS TIME SPENT IN DRILLING THE DEPTH. SHUT DOWN TIME IS SPENT SHUT DOWN FOR REPAIRS, ROUND TRIPS, WATER, ETC. SHOW WHEN BIT IS CHANGED AND KIND OF NEW BIT. MENTION ROUND TRIPS IN REMARKS COLUMN. FILL OUT THIS FORM FROM TOP TO BOTTOM OF HOLE.

4-6-01