

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

15101-20091-0000 Form CP-4

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Lane _____ County. Sec. 23 Twp. 20 Rge. _____ (E) 30 (W) _____
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner HERNDON DRILLING CO.
Lease Name Stulken Well No. 1
Office Address Box 489, Tulsa, Okla. 74101
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-12 19 74
Application for plugging filed 2-12 19 74
Application for plugging approved 3-12 19 74
Plugging commenced 3-12 19 74
Plugging completed 3-12 19 74
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 710 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	311	8-5/8"	303	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 750', plug, 110 sx cement;
Fluid to 310', plug, 30 sx cement;
Fluid to 40', 1/2 sx hulls, plug, 10 sx cement;

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1974
3-20-74
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor D N. B. DRILLING, INC.
Address 701 First Nat'l Bldg., Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF _____ ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of March 19 74

My commission expires 8-25-76

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976

Ella Priess
Notary Public.

DRILLERS' LOG

15101200910000

HERNDON DRILLING CO.
No. 1 Stulliken
C SW SW, Sec. 23-20S-30W
Lane County, Kansas

Elevation: 2871 K.B.

Commenced: 3-2-74
Completed: 3-12-74

Surface Casing: 303' of
8-5/8" cemented w/185 sx
common cement, 2% Gel, 3%cc.
3-3-74

FORMATION

DEPTH

Surface Hole	0 - 311
Shale & Sand	311 - 1555
Blaine Anhydrite	1555 - 1568
Sand & Shale	1568 - 2144
Stone Corral Anhy.	2144 - 2168
Shale & Shells	2168 - 2270
Shale & Lime	2270 - 2570
Lime & Shale	2570 - 3615
Lime	3615 - 4710 T.D.

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1974
CONSERVATION DIVISION
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 19th day of March, 1974.

My Commission Expires:
August 25, 1976

Ella Priess
Ella Priess, Notary Public

Ella Priess
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Com. Expires Aug. 25, 1976