


WELL PLUGGING RECORD

15 101-20546 0000

Give All Information Completely  
 Make Required Affidavit

COUNTY Lane SEC. 28 TWP. 16S RGE. 27W  
 Location as in quarters or footage from lines:  
SE SE NW



Locate Well  
 correctly on above  
 Section Platt.

Lease Owner White & Ellis Drilling, Inc.  
 Lease Name Johnson Well No. 1  
 Office Address Box 448, El Dorado, Kansas 67042  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed 7/7/81  
 Application for plugging filed 7/7/81  
 Plugging commenced 7/7/81  
 Plugging completed 7/7/81 3 p.m.  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4495'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	Surface	0	308'	8-5/8"	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

1st plug @ 900' with 60 sacks 50/50 Poz, 6% gel  
 2nd plug @ 320' with 30 sacks 50/50 Poz, 6% gel  
 Top plug @ 40' with 10 sacks 50/50 Poz, 6% gel  
 5 sacks in rat hole  
 Job complete @ 3 p.m. 7/7/81

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 23 1981  
 7-23-81

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet) Wichita, Kansas

Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


James C. Remsberg, Slawson Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg  
200 Douglas Bldg., Wichita 67202  
 (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 81

Mary Lou Taylor  
 Mary Lou Taylor Notary Public.

Notary expires: January 17, 1985



DRILLERS LOG

15-101-20546-0000

OPERATOR: White & Ellis Drilling, Inc.  
 Box 448  
 El Dorado, Kansas 67042

WELL NAME: #1 Johnson  
 SE SE NW Sec.28-16S-27W  
 Lane County, Kansas

CONTRACTOR: White & Ellis Drilling, Inc.  
 Box 448  
 El Dorado, Kansas 67042

COMMENCED: 6/28/81

COMPLETED: 7/7/81

RTD: 4495

SURFACE CASING: 8-5/8" set at 308' with 225 sx cement

0' to 312' Surface Hole  
 312' to 690' Shale  
 690' to 1667' Shale & Shells  
 1667' to 2113' Shale  
 2113' to 2157' Anhydrite  
 2157' to 2545' Shale  
 2545' to 3530' Shale & Lime  
 3530' to 3963' Lime & Shale  
 3963' to 4495' Lime  
 RTD 4495'

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 23 1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.  
 hereby state the above is an accurate copy of the #1 Johnson log  
 for White & Ellis Drilling, Inc.

*James C. Remsberg*  
 James C. Remsberg

Subscribed and sworn to me  
 this 21 day of July, 1981

*Mary Lou Taylor*  
 Mary Lou Taylor, Notary

My commission expires January 17, 1985

