


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Lane _____ County. Sec. 28 Twp. 16 Rge. 27 (E) _____ (W) _____
Location as "NE/CNW%SW%" or footage from lines C SW NE
Lease Owner Raymond Oil Co., Inc.
Lease Name Leighton #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3/17/70 _____ 19____
Plugging completed 3/23/70 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4640 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	296	none
				5 1/2"	4640'	1502'

RECEIVED
STATE CORPORATION COMMISSION
APR 7 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 4000', ran sand to 3950' and dumped 5 sacks of cement.
Rigged up over 5 1/2", shot pipe at 1690', 1500', worked pipe loose and pulled 48 joints. Allied pumped 1 sack hulls, 14 sacks mud, 100 sacks cement, 11 sacks mud, 25 sacks cement, 5 sacks mud, 10 sacks of cement to plug well.


PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 1970



My commission expires 2/15/71 Notary Public.

JUN 3 1961

DRILLERS LOG

Leighton No. 1

15-107-0001-0000

CASING RECORD: COMPANY: Pet-Ex Company DESCRIPTION: C SW NE
 3 5/8" @ 294' w/200 sx cement CONTRACTOR: Rod Tiger Drilling Co. 28-16S-27W
 5 1/2" @ 4640' w/150 sx cement COMPLETED: January 21, 1961 Lane County, Kansas
 ELEVATION: 2693 RB
 TOTAL DEPTH: 4640' 83 Bopd

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 26 1970 TO
 CONSERVATION DIVISION
 Wichita, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod Shale	0	85	
Sand	30	85	
Shale	85	295	
Chalky Lime	295	370	
Shale Shells	370	995	Top 3674
Sand Shale	995	1170	Heel 3933
Shale Shells	1170	1360	
Shale & Shells	1560	2115	Top 3952
Anhydrite	2115	2150	
Shale Shells	2150	2625	Base 3970
Shale & Shells	2625	2805	BKC 4279
Shale Lime	2805	3035	
Lime	3035	3045	File 4468
Lime & Shale	3045	3110	Chert 4497
Lime Shale	3110	3357	
Lime & Shale	3357	3460	Cong Chert 4555
Lime Shale	3460	3640	
Lime & Shale	3640	3690	Miss 4580
Lime Shale	3690	3910	
Lime	3910	4173	
Lime Shale	4173	4237	
Lime	4237	4558	
Chert	4558	4574	
Cherty Lime	4574	4605	
Lime	4605	4640	

T.D.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle
 George A. Angle

Subscribed and sworn to before me this 24th day of January, 1961.

Melvin Head
 Notary Public

My Commission Expires: 11-17-62