

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-101-20469-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Lane _____ County. Sec. 27 Twp. 16S Rge. 27W EOW
Location as "NE/4NW/4SW/4" or footage from lines _____
SE SW NW

Lease Owner White & Ellis Drilling, Inc.
Lease Name _____ Jones _____ Well No. 1

Office Address Box 448, El Dorado, Kansas 67042

Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole

Date Well completed 7/24/80 19

Application for plugging filed 7/24/80 19

Application for plugging approved 7/24/80 19

Plugging commenced 7/24/80 19

Plugging completed 7/24/80 9:45 a.m. 19

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____

Show depth and thickness of all water, oil and gas formations. _____ TD 4000'

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	343'	8-5/8"	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 800' with 70 sacks

2nd plug @ 320' with 20 sacks

3rd plug @ 40' with 10 sacks

5 sacks in rathole

Job complete @ 9:45 a.m. 7/24/80

J.S. Taylor

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

James C. Remsberg of Slawson Drilling Co., Inc. (employee of owner) or (owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct, So help me God.


(Signature)

James C. Remsberg
James C. Remsberg
200 Douglas Building,
(Address)

SUBSCRIBED AND SWORN TO before me this 2 day of August, 19 80

Mary Lou Taylor
Mary Lou Taylor Notary Public.

My commission expires January 17, 1981



DRILLERS LOG

15-101-20469-0000

OPERATOR: White & Ellis Drilling, Inc.
 Box 448
 El Dorado, Kansas 67042

WELL NAME: Jones #1
 SE SW NW Sec. 27-16S-27W
 Lane County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 7/18/80

COMPLETED: 7/24/80

RTD: 4000'

SURFACE CASING: 8-5/8" set at 343' with 200 sx cement

0' to 346' Shale & Sand (346' 12 1/4" Surface Hole)
 346' to 2128' Shale & Sand
 2128' to 2412' Shale
 2412' to 3006' Shale & Lime
 3006' to 3264' Lime & Shale
 3264' to 3368' Shale
 3368' to 3671' Lime & Shale
 3671' to 3788' Shale & Lime
 3788' to 3966' Lime
 3966' to 4000' Limestone (Lansing)
 RTD 4000'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
 hereby state the above is an accurate copy of the Jones #1 log for
 White & Ellis Drilling, Inc.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to
 me this 2nd day of August, 1980

Mary Lou Taylor
 Mary Lou Taylor Notary

My commission expires January 17, 1981

