

1 070239

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20,772-0000  
C N/2 SW, SEC. 28, T 16 S, R 27 W 28  
1980 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113  
Operator: Landmark Companies  
Name & Address 110 South Main, Suite 510  
Wichita, KS 67202

Lease Name Hall Well # 1  
County \_\_\_\_\_ Lane 150.05  
Well Total Depth 4617 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:50 a.m. Day: 29 Month: 10 Year: 1986

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4616' PBD 4110' Perfs 4070-4084'

1st plug sand back to 3950' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 100 sx cement down 4 1/2" annulus, 70 sx cement down 8 5/8" annulus.

Plugging Proposal Received by Don Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:20 a.m. Day: 29 Month: 10 Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded back to 3950' and dumped 4 sx cement on top of sand with bailer.

2nd plug pumped 100 sx cement down 4 1/2" annulus and 70 sx cement down 8 5/8" annulus.

4 1/2" Maximum pressure 1200 psi and shut in 500 psi.

8 5/8" Maximum pressure 300 psi and shut in 300 psi.

Remarks: Used Thrifty Mix by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
id ~~XXXXXX~~ observe this plugging.

DATE 11-3-86

Signed Don Ubel  
(TECHNICIAN)

INV. NO. 15289

10-29

11-3-86  
NOV