

1 070750

11-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,277-0000
SW SE SE, SEC. 28, T 16 S, R 27 W/R

330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Beougher Well # 1

Operator: A.L. Abercrombie, Inc.
Name & Address 801 Union Center Building
Wichita, KS 67202

County Lane 149.14
Well Total Depth 4589 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor A.L. Abercrombie, Inc. License Number 5393

Address 801 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 11:15 a.m. Day: 1 Month: 11 Year: 1989

Plugging proposal received from E.L. Abercrombie

(company name) A.L. Abercrombie, Inc. (phone) 316-262-1841

were: 4 1/2" at 4361' PBTD 4344' Perfs at 4074-4224' (3 sets) Elevation 2708' GL

1st plug pump 500 lbs. hulls and 75 sx Econolight to 1200',

2nd plug perforate at 1100', fill 4 1/2" with cement and squeeze 50 sx cement through
perf. at 1100',

3rd plug pump 75 sx cement through 8 5/8" X 4 1/2" annulus from top.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 1 Month: 11 Year: 1989

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls in first part of 80 sx ATL cement
down 4 1/2", displaced to 1368' with fresh water to 1500 lbs.

2nd plug perforated 4 1/2" at 1100', pumped 125 sx 65/35 Pozmix 8% gel down casing displacing
50 sx through perfs. Maximum pressure 600 psi and shut in 100 psi.

3rd plug pumped 75 sx 65/35 Pozmix 8% gel down 8 5/8" X 4 1/2" annulus. Maximum pressure
100 psi and shut in 100 psi.

Remarks: Used ATL and 65/35 Pozmix 8% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
NOV - 7 1989
11-7-89
CONSERVATION DIVISION
Wichita, Kansas

INVOICED
DATE 11-18-89
INV. NO. 26374

Signed Dar Gooden
(TECHNICIAN)