

To: 1031361
STATE CORPORATION COMMISSION
Wichita State Office Bldg. 10-5 PLUGGING SECTION
430 S. Market, Room 2078
Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6040
Operator: Bankoff Oil Company
Name: P.O. Box 700657
Address: Tulsa, OK 74170

API NUMBER 15- 101-21,712
SE NW NE, SEC. 25, T. 16 S, R. 27 W/EK
990 feet from N section line
1650 feet from E section line
Lease Name Klitzke Well # 1
County Lane 151.13
Well Total Depth 4650 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well Gas Well Input Well SMD Well O&A X

Other well as hereinafter indicated

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address: P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 6 p.m. Day: 5 Month: 10 Year: 1995

Plugging proposal received from Judy

(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2106-2140'

1st plug at 2130' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,

3rd plug at 780' with 50 sx cement, 4th plug at 300' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant

Plugging Operations attended by Agent?: All Part 10-9-95 None X

Operations Completed: Hour: 8 p.m. Day: 5 Month: 10 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement,

2nd plug at 1320' with 80 sx cement,

3rd plug at 780' with 50 sx cement,

4th plug at 300' with 40 sx cement,

5th plug at 40-0' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.)

DATE 10-17-95

INV. NO. 43794

Signed Steve Durrant
(TECHNICIAN)

10-5 DEC 07 1995