

To: 1 071125 11-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,376 & 0001 252
SE NE SW, SEC. 23, 'T 16 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: Kansas Corporation Commission
Name: _____
Address: _____

1650 feet from S section line
2970 feet from E section line
Lease Name Stremel Well # 1-R
County Rush
Well Total Depth 3620 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1146

Abandoned Oil Well KCC op Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor KCC License Number _____
Address _____

Company to plug at: Hour: 12:25 p.m. Day: 3 Month: 11 Year: 19 92

Plugging proposal received from Dan Goodrow
(company name) KCC (phone) 913-798-3338

Perfs: 5 1/2" at 3620' w/200 sx cement. PBTD 3380'. Perfs at 3364-70'
1st plug pump 300 lbs. hulls, 20 sx cement, 20 sx gel, 80 sx cement down 5 1/2".

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 3 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls, 20 sx cement, 20 sx gel, 80 sx cement down 5 1/2".

Maximum pressure 2000 psi and shut in 0 psi.

Previously plugged-100 sx cement down backside.

Remarks: Used 60/40 Pozmix 8% gel by B.J. Services. No casing recovery.
(if additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.
Signed Dan Goodrow (TECHNICIAN)