

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-165-21,098-00-00
NE4, Sec. 20, T 16 S, R 17 W X
1320 feet from N X section line
1500 feet from X/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5267

Lease Name MERMIS Well # 1

Operator: K&E PETROLEUM, INC.
Name & Address 100 S. MAIN, STE. 300
WICHITA, KS 67202

County RUSH

Well Total Depth 3583 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1122

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE DRILLING, INC. License Number _____

Address 801 UNION CENTER, WICHITA, KS 67202

Company to plug at: Hour: 11pm Day: 29 Month: Dec Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Wilmer Drilling

(company name) Abercrombie (phone) _____

were: to use 50/50 Permox, 4% gel, 3% CC. & locate 1st plug
at 1140' w/70 sq. cnt.; 2nd plug @ 750 w/40 sq.
cnt.; 3rd @ 40' w/1/2 sq bulls. & 8 5/8 plug; 4th @
40'-0' w/10 sq.; 5th by circ. 10 sq. cnt. in
rat hole.

Signed R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:45pm Day: 29 Month: Dec Year: 19 82

ACTUAL PLUGGING REPORT Plugged as ordered.

Cementing by Sun.

Remarks: Anhydrite top at 1119'
8 5/8 cemented w/500 sq. Common 2% gel-3% CC. Circ.

I hereby certify that the above plugging instructions were given as herein stated
and that I ~~was~~ / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
01-04-1983
JAN 04 1983
CONSERVATION DIVISION
Wichita, Kansas

Signed R. Barluttan
(TECHNICIAN)

1-18-83
2180-w