

1090066

4-20

191 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 165-20,028-00-00

C NE SW, SEC. 19, T 16 S, R 17 W/E

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456

Lease Name Hooper Well # 2

Operator: AFG Energy, Inc.

County Rush 115.15

Name & Address P.O. Box 605

Well Total Depth 3543 feet

Russell, KS 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor AFG Energy, Inc. License Number 3456

Address P.O. Box 605, Russell, KS 67665

Company to plug at: Hour: 12 p.m. Day: 20 Month: 4 Year: 19 90

Plugging proposal received from Terry W. Piesker

(company name) AFG Energy, Inc. (phone) 913-483-6213

were: 4 1/2" at 3535' PBDT 3492' Perfs at 3363-3154' DV at 1106' w/550 sx cement

1st plug pump 5 sx hulls, 50 sx common cement, and fill with 60/40 Pozmix 6% gel.

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 20 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 500 lbs. hulls, 50 sx common cement, and 245
sx 60/40 Pozmix 6% gel. Maximum pressure 2000 psi and shut in 1000 psi.

Hooked up to 8 5/8" X 4 1/2" annulus and checked maximum pressure 500 psi and
shut in 500 psi.

Remarks: Used common cement and 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED (If you observe this plugging.)

DATE 5-3-90

INV. NO. 28013

APR 30 1990
04-30-1990
CONSERVATION DIVISION
WICHITA, KANSAS

Signed Michael P. Wilson
(TECHNICIAN)