

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-30150-00-00
Spot: CSEENENW Sec/Twnshp/Rge: 19-16S-17W
990 feet from N Section Line, 1650 feet from W Section Line
Lease/Unit Name: HOOFER Well Number: 1
County: RUSH Total Vertical Depth: 3527 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 603 MAIN AVE., STE 500
KNOXVILLE, TN 37902

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 220 WITH 135 SX CMT #114.63
Production: Size 4.5 feet: 3525 WITH 275 SX CMT
Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/24/2001 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ED GLASSMAN Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: RUN TUBING AND PUMP 25 SX CMT. @ 3175'. PULL TUBING UP TO ANHYDRITE AND CIRCULATE 75 SX TO SURFACE. PULL TUBING. TIE ONTO BACKSIDE AND PRESSURE UP THE ANNULAS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/24/2001 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 3488'. PERFS AT 3249-53, 3269-73, 3311-15, 3325-29, 3338-44'. 2 STAGED AT 1101' WITH 320 SX CMT. RUN TUBING TO 3100' AND MIX 30 SX CMT WITH 150# HULLS AND DISPLACED DOWN TO BOTTOM. PULL TUBING TO 1100' AND CIRCULATE CMT. USED 75 SX CMT & 200# HULLS. CMT DID CIRCULATE. PULLED TUBING AND USED 15 SX CMT TO TOP OFF. TIED ONTO BACKSIDE AND MIXED 20 SX CMT. PRESSURED TO 500# AND HELD.

INVOICED
DATE 03-08-2001
JV. NO. 2001061450

01-31-2001

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Michael J Maier
(TECHNICIAN)

JAN 30 2001

MP

AMY