

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-00359-00-00
Spot: SENESE Sec/Twnshp/Rge: 19-16S-17W
1665 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: LIPPERT Well Number: 2
County: RUSH Total Vertical Depth: 3517 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 603 MAIN AVE., STE 500
KNOXVILLE, TN 37902

Conductor Pipe: Size feet: 5.5 3517 WITH 135 SX CMT
Surface Casing: Size 8.625 feet: 222 WITH 175 SX CMT
Production: Size 5.5 feet: 3517 WITH 175 SX CMT
Liner: Size feet: 5.5 3517 WITH 175 SX CMT

\$114.30

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/22/2001 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ED GLASSMAN Company: TENGASCO Phone: (785) 625-6374

Proposed Plugging Method: RUN TUBING AND PUMP 75 SX CMT & 300 # HULLS @ 3160'. PULL TUBING UP TO ANHYDRITE AND CIRCULATE 125 SX CMT. TO SURFACE. PUL TUBING. TIE ONTO BACKSIDE AND PRESSURE UP THE ANNULAS.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/23/2001 1:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3208. PERFS @ 3172-3180'. DV @ 1122' WITH 475 SX CMT. RAN TUBING TO 3130'. PUMPED 100# HULLS & 25 SX CMT DISPLACED TO BOTTOM. PULLED TUBING TO 1122'. PUMPED 200# HULLS & 170 SX CMT. NO CIRCULATION. ON 01/23/01 RAN TUBING IN HOLE. TAGGED CMT AT 2139'. PULLED TUBING TO 1116'. COULD NOT GAIN CIRCULATION. SET BRIDGE PLUG AT 1100'. RAN TUBING TO 1070'. PUMPED 120 SX CMT, CIRCUALTING IT TO SURFACE. PULLED TUBING AND TOPPED OFF HOLE WITH 10 SX CMT. PRESSURED 8 5/8 X 5 1/2 ANNULUS TO 500 PSIG WITH 5 SX CMT.

INVOICED
DATE 03-08-2001
INV. NO. 2001061450

01-31-2001

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

JAN 26 2001

Form CP-2/3

MP

AMT