

1-13

1-120877

15-165-00303-00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: Drilled 6/20/63

recap
2970 SW SE NE /4 SEC. 18, 16 S, 17 W
2790 feet from S section line
990 feet from E section line

Operator license# 3456 Lease Schlitter well # 1

Operator: AFG Energy Inc. County Rush

Address: P.O. Box 458 Well total depth 3560 feet *115.70*
Hays, KS 67601-0458 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 951 feet

Aband. Oil well , Gas well X, Input well , SWD , D & A

Plugging contractor: AFG Energy Inc. License# 3456

Address: P.O. Box 458, Hays, KS 67601-0458

Company to plug at: Hour: 9:30 am Day: 13 Month: January Year: 1994

Plugging proposal received from: Terry Piesker

Company: AFG Energy Inc. Phone: 913-625-6374

Were: 4 1/2" at 3558' w/275 sx cement, Perfs at 2900-3343' (5 sets) PBSD 3410'
1st plug pump in 4 1/2" casing with 400 lbs. hulls and 150 sx cement.
2nd plug pump in 8 5/8" x 4 1/2" annulus with 150 sx cement.

Plugging Proposal Received by: Duane Rankin
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11 a.m., Day: 13, Month: January, Year: 1994

Actual plugging report: 1st plug pumped into 4 1/2" casing with 400 lbs. hulls and 190 sx cement. Pumping pressure 0-500 psi and shut in 400 psi.
2nd plug pumped into 8 5/8" X 4 1/2" annulus with 160 sx cement. Pumping pressure 0-100 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 8% gel by Allied. Recovered no casing.

I did[X] / did not[] observe the plugging.

Duane Rankin

RECEIVED
STATE CORPORATION COMMISSION
(agent)

Form CP-2/3
JAN 21 1994
01-21-1994
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-24-94
INV. NO. 39753