

1051795

3-31

15-165-00132-00-01

API NUMBER 15- 3/4/63

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 17, T 16 S, R 17 W/8
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3456
Operator: AFG Energy Inc.
Name: P.O. Box 458
Address: Hays, KS 67601

Lease Name Hartman "A" Well # 1
County Rush
Well Total Depth 3540 115.05 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1147

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address Russell, KS

Company to plug at: Hour: 10 a.m. Day: 31 Month: 3 Year: 19 94

Plugging proposal received from Terry Piesker
(company name) AFG Energy Inc. (phone) 913-625-6374

logs: 4 1/2" at 3540' w/200 sx cement, 3064-3526' (11 sets) Perforations, Pumped 150 sx cement down 8 5/8" on 5/13/88.

1st plug fill casing with cement,

Check backside.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:35 a.m. Day: 31 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 500 lbs. hulls and 225 sx cement.

Maximum pressure 0 psi and shut in 0 psi.

Pressured backside to 500 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

INVOICED

(Additional description is necessary, use BACK of this form) observe this plugging.

DATE APR 08 1994

INV. NO. 40270

3-31

Signed

Richard W. Lutz

RECEIVED
STATE CORPORATION COMMISSION
04-05-1994
APR 05 1994
TECHNICIAN
CONSERVATION DIVISION
Wichita, Kansas FORM 1
REV.