

12-3-87

To: 1 070484
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,328-10001
NW SE SE, SEC. 29, T 16 S, R 27 ~~W~~
990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629
Operator: Brito Oil Company, Inc.
Name & Address 200 East First, Suite 208
Wichita, KS 67202

Lease Name Massey Well # 1-29
County Lane 150.96
Well Total Depth 4645 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929
Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 3 a.m. Day: 3 Month: 12 Year: 19 87

Plugging proposal received from Ervin Neighbors

(company name) Duke Drilling Company (phone) 316-267-1331
were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2714'
Anhydrite 2125-65'

1st plug at 2165' with 50 sx cement, 2nd plug at 1360' with 75 sx cement,
3rd plug at 360' with 45 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:45 a.m. Day: 3 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2165' with 50 sx cement,
2nd plug at 1360' with 75 sx cement,
3rd plug at 360' with 45 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
12-7-87
DEC 7 1987

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-8-87

Signed Dan Jordan
(TECHNICIAN)

INV. NO. 19194 JAN 14 1988
12-3