

1 070218

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,328-0000
NW SE SE, SEC. 29, T 16 S, R 27 ^{W/E}
990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4865
Operator: SunTex Resources, Inc.
Name & Address 12160 Abrams St., Suite 417
Dallas, TX 75243

Lease Name Massey Well # 1-29
County Lane 150.96
Well Total Depth 4645 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling License Number 9087
P.O. Box 296
Address Hays, KS 67601

Company to plug at: Hour: 7:30 p.m. Day: 3 Month: 9 Year: 19 86

Plugging proposal received from John Weis

(company name) R & C Drilling (phone) 913-625-4548

was: to fill hole with heavy mud and spot cement through drill pipe Elevation 2714 GL

- 1st plug at Anhydrite with 50 sx cement
- 2nd plug at Base Cheyenne with 80 sx cement
- 3rd plug at 30' below base of surface casing with 40 sx cement
- 4th plug at 40' to surface with 10 sx cement
- 5th plug to circulate rathole with 15 sx cement
- 6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11 p.m. Day: 3 Month: 9 Year: 19 86

- ACTUAL PLUGGING REPORT
- 1st plug at 2165' with 50 sx cement
 - 2nd plug at 1360' with 75 sx cement
 - 3rd plug at 360' with 45 sx cement
 - 4th plug at 0-40' with 10 sx cement
 - 5th plug to circulate rathole with 15 sx of cement

Remarks: Used 60/40 Pozmix 6% gel by Allied
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 10 1986

INV. NO. 4910

SEP 9 1986
9-9-86

Signed Dan Godwin
(TECHNICIAN)