

1 070856

10-1

15-101-20278-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-23,718-X

NE SE NE, SEC. 29, T 16 S, R 27 W/E

3730 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Hall Well # 1

Operator: A.L. Abercrombie, Inc.

County Lane Lane 149.50

Name & Address Route 1, Box 56

Well Total Depth 4600 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 293

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor A.L. Abercrombie, Inc. License Number 5393

Address Route 1, Box 56, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 1 Month: 10 Year: 19 90

Plugging proposal received from R.D. Rapp

(company name) A.L. Abercrombie, Inc. (phone) 316-793-8186

were: 5 1/2" at 2140' w/600 sx cement. PBSD 2140'. Perfs at 1715-1860'

Casing cemented 2140'-0.

1st plug pump 300 lbs. hulls and 100 sx cement,

2nd plug pump 50 sx cement down backside.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 1 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 600 lbs. hulls and 120 sx ATL cement down 5 1/2".

Maximum pressure 1200 psi and shut in 300 psi.

Backside would not take at 1000#.

Remarks: Used ATL cement by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

10-8-90
OCT 8 1990

INVOICED observe this plugging.

Signed Dan Anderson
(TECHNICIAN)

DATE 10-18-90

INV. NO. 29649