

1091053

TO: STATE CORPORATION COMMISSION

API NUMBER 15-135-24,101-00-00
NE NE SW SEC. 14, T 20 S, R 26 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME DINGES WELL # 1-14

TECHNICIAN'S PLUGGING REPORT COUNTY NESS 146.90

OPERATOR LICENSE # 31021 5/24 WELL TOTAL DEPTH 4520 FEET

OPERATOR: CASTELLI EXPLORATION, INC. PRODUCTION CSG: SIZE " FEET

NAME AND 9500 WESTGATE DRIVE, SUITE 101 SURFACE CASING: SIZE 8 5/8" @ 221' WITH SX

ADDRESS OKLAHOMA CITY, OK 73162

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DISCOVERY DRILLING, INC LICENSE NUMBER 31548

ADDRESS PO BOX 763, HAYS, KS 67601

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 24 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM TOM

(COMPANY NAME) DISCOVERY DRILLING, INC (PHONE) 785-623-2920

WERE:

1ST PLUG AT 1755' WITH 50 SX CEMENT, 2ND PLUG AT 900' WITH 80 SX CEMENT.

3RD PLUG AT 240' WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH

10 SX CEMENT.

 PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE X

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 24 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT LOAD HOLE WITH HEAVY MUD SPOT PLUGS THRU DRILL PIPE

1ST PLUG AT 1755' WITH 50 SX CEMENT, 2ND PLUG AT 900' WITH 80 SX CEMENT. 3RD PLUG AT 240'

WITH 40 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT. 5TH PLUG TO CIRCULATE RAT HOLE WITH

15 SX CEMENT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED INVOICED

DATE 6/9/00

WEL. NO. 61845

RECEIVED
STATE CORPORATION COMMISSION
06-06-2000
JUN 6 2000

CONSERVATION
Wichita, KS
FORM CP-2/3