

To: 1 093297 6-17
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,747-00-00
SE SE SE, SÈC. 13, T 20 S, R 26 WXE

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782
Operator: Ensign Operating Company
Name &
Address 621 17th St., Ste. 1800
Denver, CO 80293

330 feet from S section line
330 feet from E section line
Lease Name Johnson Well # 1-13
County Ness
Well Total Depth 4535 147.38 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service, Inc. License Number 6907
Address P.O. Box 458, Ness City, KS 67560-0458

Company to plug at: Hour: 1 p.m. Day: 17 Month: 6 Year: 19 93

Plugging proposal received from Roger Pearson
(company name) Hembree Well Service, Inc. (phone) 913-798-3408

were: 4 1/2" at 4535' w/150 sx cement, PBTD 4488', Perfs at 4446-4461'
1st plug set CIBP at 4200' with 2 sx cement on top,
2nd plug spot 50 sx cement at 1890',
3rd plug at 970' with 80 sx cement, 4th plug at 345' with 50 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45 p.m. Day: 17 Month: 6 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4200' with 2 sx cement on top,
2nd plug spotted 50 sx cement at 1890',
3rd plug at 970' with 80 sx cement,
4th plug at 345' with 50 sx cement,
5th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1993
06-21-1993

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2570' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 7-9-93
DIV. NO. 38083

Signed [Signature]
(TECHNICIAN)