

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-20360-0000

S 1/4 Sec. 31, T 31 S, R 11 W 1/4

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Swaden Well # 1

Operator:  
Name & Address Texas Oil & Gas Corp.  
200 W. Douglas, Suite 300  
Wichita Kans.  
67202

County Bahe

Well Total Depth 4331 feet 8140.73

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 263

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clark Corporation License Number 5105

Address 107 W. Lowden Medicine Lodge, Kansas 67104

Company to plug at: Hour: 10:30AM Day: 19 Month: April Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Elmo Morgenstern

(company name) Clark Corp (phone) \_\_\_\_\_

were: 1st plug sanded bottom back to 3400' & dumped  
4 bbl cement on sand. 2nd plug pumped through swedge  
up 3 bbl hulls & 15 bbl gell & 50 bbl cement 10 bbl gell  
& 1 bbl hulls & 130 bbl cement. Ann cementing accomplished  
the plugging w/ 50/50 pour w/ 2% gell & 3% C.C.

Signed Saul A. Luthis  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00AM Day: 19 Month: April Year: 1983

ACTUAL PLUGGING REPORT This hole was plugged as ordered  
given in above paragraph.

Remarks: Max pressure was 600# & shut in @ 400#  
Mr. Richard Lacy gave these orders & Paul A.  
Luthis saw it plugged They recovered 2381' of 4 1/2"  
production pipe.

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

Signed Saul A. Luthis ✓  
(TECHNICIAN)

INVOICED

DATE 4-27-83  
INV. NO. 4128-W

RECEIVED  
STATE CORPORATION COMMISSION  
APR 22 1983  
4-22-83  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 9-82